



A - *Kalmia latifolia* 'Elf' or 'Tiddlywinks' (Dwarf Mountain Laurel), 3' o.c.

B - *Phlox stolonifera* (Creeping phlox), 12" o.c.

C - *Penstemon laevigatus* (Eastern Smooth Beardtongue) or *Polystichum acrostichoides* (Christmas Fern)

D - *Hosta sieboldiana* 'Elegans' (Elegans Hosta), 2' o.c. or *Heuchera americana* (Alumroot; many cultivars)

E - *Narcissus* 'Thalia' or 'Ice Follies', 4" o.c., total 30 bulbs (White Daffodils)

Note: o.c. = on center

Direct water into the garden from adjacent turf and downspouts  
Excavate the walk and garden areas at the same time and install all soil improvements for treating the runoff in both the pavement and planting areas at the same time.

The paver area will be underlain with open graded stone and should be vertically separated from the rain gardens with a curb.



**ENTRY RAINGARDEN  
FLANKING WALK WITH  
PERMEABLE PAVERS  
113 SF GARDEN, 72 SF PAVERS**

Mountains  
Pt Shade-Shade

Zones: All

Scale: 1/4" = 1'

